

**KERALASTATE ELECTRICITY BOARD LIMITED**

(Incorporated under the Indian Companies Act, 1956)

Reg. Office :VydyuthiBhavanam, Pattom,Thiruvananthapuram – 695 004

website : www.kseb.in, CIN – U40100KL2011SGCO27424

**Office of the Deputy Chief Engineer Electrical Circle
VydyuthiBhavanam, Near Municipal Stadium,
Vidyanagar,Kasaragod**Kerala, PIN – 671123 ,Phone: **04994-230382** , 9496011431(FCT)**E-mail:dceksd@gmail.com**

No.EC-KSD/DBC/SRS-Gate/2025-26


Date: -06-2025

Re Quotation Notice No. 12/25-26

Sealed Quotations are invited from qualified and experienced contractors in similar work to carry out the following work. The quotationers are requested to send their offer through speed post/Courier in sealed covers with the quotation number and name of work superscribed. Contractors having PAN card need only apply.

Name of Work	Providing Gate at the entrance of Sub Regional Store, Kasaragod by dismantling and reconstructing the partially damaged existing gate and abutting compound wall and pillars.
Probable Amount of Contract	Rs.1,66,059/- (excluding GST)
Cost of Quotation Form	Nil
EMD	Rs 4200/-
Date of Sale of Quotation	10.06.2025 to 23.06.2025, 2PM
Last date and Time for the receipt of quotations	24.06.2025, 3PM
Date and time of opening of quotations:	24.06.2025, 3.30PM (If this day happens to be a holiday, the quotations will be opened on the next day at the same time)
Period of completion of work	20 Days
Name and address of officer to whom the quotation is to be sent:	Deputy Chief Engineer, Electrical Circle, Vydyuthi Bhavanam, Near Municipal Stadium, Vidyanagar, Kasaragod, (Dist), Kerala, India, Pin: 671123, Phone:04994-230382.
Name of office issuing and receiving quotation	Office of the Deputy Chief Engineer, Electrical Circle, Vydyuthi Bhavanam, Near Municipal Stadium, Vidyanagar, Kasaragod, (Dist), Kerala, India, Pin: 671123, Phone:04994-230382.

Further details can be had from this office during office hours on all working days


Deputy Chief Engineer
Electrical Circle
Kasaragod

100
ATC

2500

Copy Submitted to:

(1) The Chief Engineer, Distribution North Malabar, Vidyuthi Bhavanam, Kannur.

Copy to: (1) The Secretary,

Municipality, Kasaragod/Kanhangad.

(2) The Village Officer, Village Office, Muttathody Village, Chengala Village Office,
PO Chengala,, PIN-671541

(3) The Secretary, Grama Panchayath, Chengala..

(4) All Assistant Executive Engineers, Electrical Sub Division. *S.*

(5) The Assistant Executive Engineer, *Sub Regional* DC Store, Kasaragod.

(6) All Assistant Engineers, Electrical Sections, ~~Kasaragod/Kanhangad.~~

(7) AAO (O)


(8) SB1(O)

(9) AB(O)

(10) Notice Board

Conditions of Contract

1. The bidder shall specify GST status (GST Registered/ Unregistered) and quote percentage of GST rate separately) for the work in the attached schedule.
2. All statutory recoveries such as all taxes duties etc. will be recovered from the bill as per rules.
3. The payment will be effected only after satisfactory completion of the work through NEFT/RTGS. If required, a mandate in prescribed form has to be submitted by the contractor authorizing the Board to transfer the payments for the supply through RTGS/NEFT. Contractor should produce copy of PAN card, copy of Adhaar card, copy of Bank account pass book showing A/c No, IFSC code etc. and Phone number.
4. The rate/amount accepted and specified in the agreement shall not be changed on any account whatsoever, and this rate shall hold good for all items done under the contract irrespective of variations in quantities to whatever extent and/or substitution by extra items.
5. The work should be completed within 20 days from the date of execution of agreement.
6. If the work is not completed by the contractor within the stipulated period, penalty as per rules will be inflicted and the balance of the work will be arranged otherwise at the risk and cost of the contractor.
7. The undersigned reserves the right to accept or reject any or all the quotations without assigning any reason thereof.
8. No revision of agreed rate shall be allowed to the contractor during the currency of this contract or during the extended period of contract, if any.
9. The contractor shall ensure safe custody of KSEBLs materials issued to him if any.
10. The safety of workmen engaged by the contractor shall be the responsibility of contractor and KSEBL will not be responsible for any loss or damage and no compensation will be paid by KSEBL on this account.
11. All conditions, rules and other regulations prevailing in the KSE Board Ltd. for contract works are applicable to this work also.


Deputy Chief Engineer
Electrical Circle
Kasaragod

by list

KERALA STATE ELECTRICITY BOARD LIMITED

Name of work: Providing Gate at the entrance of Sub Regional Store,Kasaragod by dismantling and reconstructing the partially damaged existing gate and abutting compound wall and pillars

SCHEDULE

No	Specification	Quantity	Rate	Per unit		Amount
1	15.7.4. Demolishing Laterite masonry work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.15.7.4 In cement mortar	12.00 m3	1697.78	1	m3	20367.05
2	15.19 Dismantling steel work manually/ by mechanical means in built up sections without dismembering and stacking within 50 metres lead as per direction of Engineer-in-charge.	100.00 kg	3.19	1	kg	319.32
3	2.1.1.Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift up to 1.5 m, as directed by Engineer-in-Charge: All kinds of soil.	124.00 m3	106.91	1	m3	13256.84
4	2.6.1 Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.	4.00 m3	210.02	1	m3	840.92
5	50.6.7.1 Laterite masonry with neatly dressed laterite stones of size 40X20X15 cm or nearest size in cement mortar 1:6 for foundation and basement including cost of materials labour charges etc complete.	10.10 m3	8499.43	1	m3	85818.78
6	13.1.1 12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand) ,	43.00 m2	308.22	1	m3	13253.46
7	13.46.1. Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm).	43.00 m2	190.26	1	m2	8181.18

8	10.25.2. Steel work welded in built up sections/ framed work, including cutting, hoisting,fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	75.00 kg	151.29	1	kg	11346.83
9	10.25.2.(Modified Using departmental steel Items) Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.In gratings, frames, guard bar, ladder, railings, brackets, gates and similar work.	100.00 kg	78.10	1	kg	7809.67
10	13.48.3.Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications :13.48.3 Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture.	5.85 m2	145.36	1	m2	850.36
11	4.1.3 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:2:4 (cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	0.51 m3	7841.17	1	m3	4014.68
	Total					166059.08
	Say Total PAC					166059.00
	(Rupees On lakh Sixty six thousand and fifty nine only)					

Quoted rate by the Tenderer/Contractor:

I/We do hereby agree to execute the works detailed in the above schedule of work (strikeout which is not applicable- quote the rate in figures and words)

i) at % below the estimate rate (.)

ii) at Estimate Rate (.)

iii) at % above the estimate rate (.)

Signature of the Contractor/ bidder applicable)

Name and address of the contractor

Place

Date:

GSTN registration status of the contractor: GSTN Registered / Not Registered (Strike out which is not applicable)

In case of Registered contractor, GSTN no

Deputy Chief Engineer,Electrical Circle, Kasaragod


MR
KEL

3
566

Note:-

1. Percentage rate should be written in figure and words
2. Strike out alternatives not applicable
3. In case any obvious mistakes in the schedule for the items which can be easily identified, the contractor shall not take advantage of these errors and the department reserve the right to correct the errors wherever they are noticed after formally bringing it to the notice of the contractor during the currency contract.
4. The estimated amount is exclusive of GST. Status of GST registration (Registered/ Unregistered) shall be shown in the appropriate column. GST amount also will be taken for comparison & finalization of the tender. For example, one GST registered contractor quoted 15 % below the estimate rate and one other contractor , who have not registered in GST , has quoted at Estimate. Then, net percentage for registered contractor (considering GST as 18%) = $0.85 \times 1.18 = 100.30\%$. In this case, the contractor who has no GST registration and quoted at estimate rate is the lowest tenderer.

Signature of the contractor/ bidder


Deputy Chief Engineer, Electrical Circle, Kasaragod

*for
NELL*

25/11/17